

DATE: 09/12/2019

ADDENDUM #1

TO: Potential suppliers

FROM: The Church of the Good Shepherd

SUBJECT: The Church of the Good Shepherd Bioretention Cell

THIS ADDENDUM IS ISSUED AS A RESULT OF QUESTIONS RAISED AT THE PRE-BID MEETING. THIS INFORMATION IS HEREBY INCORPORATED INTO THE RFP.

ACKNOWLEDGEMENT VIA SIGNATURE BELOW AND INCLUDING WITH YOUR PROPOSAL SUBMISSION IS REQUIRED. FAILURE TO ACKNOWLEDGE ADDENDUM #1 WILL RESULT IN YOUR PROPOSAL BEING SET ASIDE AS NON-RESPONSIVE.

See the following changes to the design plans. The cost spreadsheet and plans have had minor changes and are posted online. Be sure to use the updated cost sheet in the bid portion of your submission.

Existing Site Conditions and Site Preparation: remove approximately 83.5 ft of existing concrete curb along the existing concrete sidewalk in preparation for the proposed concrete wall

Construction Notes: note L: Contractor shall remove approximately 83.5 ft of existing concrete curb along the existing concrete sidewalk to install the proposed concrete wall. note Q: Contractor shall include a utility trace wire for all underdrain piping outside of the bioretention footprint.

Estimated Construction Quantities: concrete curb removal

Addendum #1

Acknowledge by (print name): _____ Date: _____

Signature: _____ Company Name: _____